



92755 Allen Road
Astoria, OR 97103
P (503) 458-6461
F (503) 458-0993

kknappa@centurytel.net

Policy # 96-5
Mainline Extension/Addition

Adopted or Effective: April 20, 1992
Reviewed or Revised: March 10, 2003

1. Should a mainline extension/addition be necessary to provide service to a parcel/parcels of property, the following shall apply:
2. The full expense of the extension/addition, including all construction costs, flushing, chlorinating, pressure testing, and water sampling, shall be borne by the requesting party (Article XI, Section 1, Knappa Water Association Bylaws).
3. Extensions/additions shall be a minimum of **eight-inches** in diameter.
4. Mains, gate valves, fire hydrants, elbows, blow-off's and any and all other appurtenances shall be installed to Knappa Water Association specifications and AWWA and Oregon Health Division standards.
5. Six-inch or larger fire hydrants shall be installed every 1000 (one thousand) feet, or as prescribed by the Knappa-Svensen-Burnside fire chief.
6. Upon completion of installation, mains will be flushed, chlorinated, and pressure tested by the contractor to Knappa Water Association specifications and AWWA and Oregon Health Division standards. A water sample must be drawn and submitted to a certified laboratory for bacterial analysis.
7. The Knappa Water Association will accept ownership of the extension/addition from the requesting party (1) upon written request, accompanied by certification that the extension/addition is free of liens, and (2) certification by the Knappa Water Association operations manager that all criteria have been met. The party installing the water line will be responsible for the first year of maintenance.

SIGNATURE ON FILE

Board President